



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-20265-00-00

10-20-1969  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Johnny Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt.

Complete Address: Brewer #370, Hays, Kansas.

Lease Name: Elmer Gano Well No. 4

Location: SE-SE-NE Sec. 11 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4027' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 975'

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

N. L. Dickel

Conservation Division Agent