



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20226-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas
05-26-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mikelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mikelson guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 312 Union Center Building, Wichita, Kansas.

Lease Name: Pfeifer Well No. 1

Location: NE-NE-NW Sec. 11 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4080 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mikelson was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent