



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

30061-00-01
~~15-065-20257-00-00~~

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1974
CONSERVATION DIVISION
Wichita, Kansas
03-07-1974

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Elmer Gano Well No. 2

Location: NE-NE-NE Sec. 11 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4053' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

App: 200'--8 5/8" Surface casing, cement circulated.
4049'--4 1/2" Production casing cemented on bottom with 200 Sx. Well
plugged back to 4025'. Top perforations from 3850' to 3854'.

Push plug to 3800', sand back to 3750' and set 4 Sx. cement with dump
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent