



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.
WICHITA, KANSAS 67202

STATE RECEIVED
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

12-08-1970

15-065-20397-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt Oil Operations,

Complete Address: Drawer #370, Hays, Kansas,

Lease Name: Barney McCoy Well No. 1

Location: NW-NW-SE Sec. 13 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 3545' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

165'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1120' and displace 100 Sx.
cement thru DP. Pull DP to 185' and displace 25 Sx. cement thru DP.
Pull DP, set bridge, @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent