



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

12-02-1969

15-065-20285-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Company, has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Thelma Gano Well No. A-1

Location: NW-NE-NW Sec. 13 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4030' Oil Well

Gas Well Input Well SWD Well D-&A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent