

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1974
10-15-1974
CONSERVATION DIVISION
Wichita, Kansas

15-065-20717-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name: Buschauer Well No. 1

Location: CNW-NW Sec. 11 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth: 4040' Oil Well ---

Gas Well --- Input Well --- SWD Well --- D & A X Lost Hole ---

Mr. Bucheister was instructed to plug the well as follows:

206'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and dispaace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

R. L. Nichols
Conservation Division Agent