



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

15-065-20425-00-00

2-14-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: L. G. Stephenson,

Complete Address: 360 Sutton Place, Wichita, Kansas.

Lease Name: Bollig Well No. 1

Location: SE-SE-NE Sec. 21 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4080' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

203'--8 5/8" Surface cssing, cement circulated.

4079'-- 5 1/2" casing cemented with 125 Sx. Well plugged back to 4054'.
Top of perforations @ 3906'.

Sand well back to 3825' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 dacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent