



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
01-24-1974

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20644-00-00

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: Suite 500, 200 West Douglas, Wichita, Kansas.

Lease Name: LaCerte Well No. 1

Location: NW-NW-SW Sec. 21 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 3845' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent