



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065 - 20547-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1972
05-24-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Faulkner Well No. 1

Location: CNE-NE Sec. 28 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3810' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Davis was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,


Conservation Division Agent