



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1973
01-04-1973
CONSERVATION DIVISION
Wichita, Kansas

15-065-20585-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this

date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 1000 Century Plaza, Wichita, Kansas.

Lease Name: Fritts Well No. 1

Location: N/2-NW-NE Sec. 29 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3590' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

~~Bucheister~~ Mr. Bucheister was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent