

State of Kansas.



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
06-06-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

18-065-20231-00-00

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Faulkner Well No. 1

Location: CNE-SE Sec. 34 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3822' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

206'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 725'

Circulate hole with heavy mud. Pull DP to 950' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent