

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32278
Name: Tengasco, Inc.
Address: PO Box 458
City/State/Zip: Hays, KS 67601
Purchaser: Coffeyville Resources
Operator Contact Person: Gary Wagner
Phone: (785) 625-6374
Contractor: Name: Anderson Drilling
License: 33237
Wellsite Geologist: Rod Tremblay

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

<u>9-6-06</u>	<u>9-13-06</u>	<u>10-23-06</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 163-23554-0000
County: Rooks
NE NW SE NE Sec. 11 Twp. 10 S. R. 20 East West
1350 feet from S / NE (circle one) Line of Section
800 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Croffoot A Well #: 10
Field Name: Marcotte
Producing Formation: Arbuckle
Elevation: Ground: 2213' Kelly Bushing: 2218'
Total Depth: 3824' Plug Back Total Depth: 3793'
Amount of Surface Pipe Set and Cemented at 250' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 1645' Feet
If Alternate II completion, cement circulated from 1645'
feet depth to surface w/ 210 sx cmt.

Drilling Fluid Management Plan *Alt. II KGR 11/2/07*
(Data must be collected from the Reserve Pit)
Chloride content 1200 ppm Fluid volume 150 bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Gary Wagner
Title: Production Manager Date: 11-20-06
Subscribed and sworn to before me this 20th day of Nov.
2006
Notary Public: Leads R. J. J. J.
Date Commission Expires: 2/5/08

KCC Office Use ONLY
 Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
NOV 22 2006
KCC WICHITA

Operator Name: Tengasco, Inc. Lease Name: Croffoot A Well #: 10
 Sec. 11 Twp. 10 S. R. 20 East West County: Rooks

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: _____ Dual Induction, Neutron Density, Micro CBL/Gr	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>Anhydrite</td> <td>1667'</td> <td>+551'</td> </tr> <tr> <td>Heebner</td> <td>3427'</td> <td>-1206'</td> </tr> <tr> <td>Toronto</td> <td>3451'</td> <td>-1233'</td> </tr> <tr> <td>LKC</td> <td>3465'</td> <td>-1247'</td> </tr> <tr> <td>BLKC</td> <td>3673'</td> <td>-1275'</td> </tr> <tr> <td>Arbuckle</td> <td>3752'</td> <td>-1534'</td> </tr> </table>	Name	Top	Datum	Anhydrite	1667'	+551'	Heebner	3427'	-1206'	Toronto	3451'	-1233'	LKC	3465'	-1247'	BLKC	3673'	-1275'	Arbuckle	3752'	-1534'
Name	Top	Datum																				
Anhydrite	1667'	+551'																				
Heebner	3427'	-1206'																				
Toronto	3451'	-1233'																				
LKC	3465'	-1247'																				
BLKC	3673'	-1275'																				
Arbuckle	3752'	-1534'																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23#	250'	Com	160	2% gel, 3% CC
Production	7-7/8"	5-1/2"	14#	3817'	ASC	185	2%gel, 10% salt

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input checked="" type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	0 - 1645'	60/40 Poz	210	6% gel, 1/4# flocele/sx

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
6	3754.5 - 56.5'	3000 gal 15% NeFe, 5100 bbl polymer	

TUBING RECORD	Size 2-7/8"	Set At 3750'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. 10-23-06		Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls. 75	Gas Mcf	Water Bbls. 165	Gas-Oil Ratio Gravity

Disposition of Gas	METHOD OF COMPLETION	Production Interval
<input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	<input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	_____

RECEIVED
 NOV 22 2006
 KCC WICHITA

ALLIED CEMENTING CO., INC.

22027

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>9-26-06</u>	SEC. <u>11</u>	TWP. <u>10</u>	RANGE <u>20</u>	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>1:00 PM</u>	JOB START <u>1:30 PM</u>	JOB FINISH <u>4:00 PM</u>
LEASE <u>Croffoot</u>		WELL # <u>A-10</u>	LOCATION <u>ZURICH 3 W 2 S 1 1/2 W</u>		COUNTY <u>ROOKS</u>	STATE <u>KANSAS</u>	
OLD OR <u>NEW</u> (Circle one)			<u>1/4 S 1/4 E INTO</u>				

CONTRACTOR <u>CHITTO'S Well Service</u>	OWNER <u>"Same"</u>
TYPE OF JOB <u>PORT COLLAR (Circ. cement)</u>	<u>(USED 210 SK)</u>
HOLE SIZE _____	T.D. _____
CASING SIZE <u>5 1/2</u>	DEPTH <u>PBTD 3293'</u>
TUBING SIZE <u>2 7/8</u>	DEPTH _____
DRILL-PIPE _____	DEPTH _____
TOOL <u>PORT COLLAR</u>	DEPTH <u>@ 1645</u>
PRES. MAX <u>900#</u>	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	PERFS. _____
DISPLACEMENT <u>8 1/2 BBL</u>	AMOUNT ORDERED <u>2.50 SK 60</u>
	<u>1/4# FLO SEAL</u>
	<u>per SK</u>

COMMON	<u>126</u>	@	<u>1065</u>	<u>1341 90</u>
POZMIX	<u>84</u>	@	<u>5 80</u>	<u>487 20</u>
GEL	<u>10</u>	@	<u>165</u>	<u>166 50</u>
CHLORIDE		@		
ASC		@		
		@		
<u>FLO SEAL</u>	<u>53#</u>	@	<u>2 00</u>	<u>106 00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>263</u>	@	<u>1 95</u>	<u>499 70</u>
MILEAGE <u>60</u> <u>TOW MILE</u>				<u>1420 20</u>
				TOTAL <u>4021 50</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>GILANN</u>
# <u>398</u>	HELPER <u>GARY</u>
BULK TRUCK	
# <u>345</u>	DRIVER <u>BRANDON</u>
BULK TRUCK	
# _____	DRIVER _____

REMARKS:

TEST CSG TO 700#-(HELD). PORT COLLAR @ 1645 OPEN & RECEIVED VERY GOOD CIRCULATION. MIXED 210SK CEMENT, & CEMENT CIRCULATED AROUND ANNULAS. Displaced 8 1/2 BBL, Close PORT COLLAR, & TEST TO 700# (HELD) RAN 7 JBS & WASHED CLEAN. Come out OF Hole (cement DID CIRCULATE) THANKS

CHARGE TO: TEN GAS CO INC
 STREET _____
 CITY _____ STATE _____ ZIP _____

STATE REP. KCC ON LOCATION
 - Pat STAAB -

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Harry Wagner

SERVICE

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>955 00</u>
EXTRA FOOTAGE _____	@ _____
MILEAGE <u>60</u>	@ <u>6 00</u> <u>360 00</u>
MANIFOLD _____	@ _____
	@ _____
	@ _____
TOTAL <u>1315 00</u>	

PLUG & FLOAT EQUIPMENT

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
TOTAL _____	

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: **26027**
Russell

DATE 9-6-06	SEC. 11	TWP. 10 S	RANGE 20 W	CALLED OUT 6:00AM	ON LOCATION 8:00AM	JOB START 9:30AM	JOB FINISH 10:00AM	
LEASE CROFFOOT		WELL# A-10	LOCATION Palco 2E 2S 1/2 E		COUNTY ROCKS	STATE KANSAS		
OLD OR <input checked="" type="radio"/> NEW (Circle one)			1/4 W INTO					

CONTRACTOR **A-A DALG. Rig #1**

TYPE OF JOB **SURFACE**

HOLE SIZE **12 1/4** T.D. **251'**

CASING SIZE **8 5/8 New** DEPTH **250'**

TUBING SIZE **23#** DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. **15'**

PERFS. _____

DISPLACEMENT **15/BBL**

EQUIPMENT

PUMP TRUCK CEMENTER **GILLEN**

398 HELPER **GARY**

BULK TRUCK

345 DRIVER **DOUG**

BULK TRUCK

_____ DRIVER _____

REMARKS:

Cement
CIRCULATED

THANKS

CHARGE TO: **TEN GASCO, Inc.**

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *Harry Wagner*

OWNER _____

CEMENT

AMOUNT ORDERED **160 sk Comm.**

2% GEL

3% CC

COMMON	160	@	10 65	1704 00
POZMIX		@		
GEL	3	@	16 65	49 95
CHLORIDE	5	@	46 60	233 00
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	168	@	1 90	319 20
MILEAGE	60	@	15 70	957 20
				TOTAL 3213 40

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ **215 00**

EXTRA FOOTAGE _____ @ _____

MILEAGE **60** @ **6 00** **360 00**

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 1175 00

PLUG & FLOAT EQUIPMENT

8 5/8 Plug @ **60 00**

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL 60 00

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: 26034

Russell
9-14-06

DATE <u>9-13-06</u>	SEC. <u>11</u>	TWP. <u>10</u>	RANGE <u>20</u>	CALLED OUT <u>6:30PM</u>	ON LOCATION <u>8:00PM</u>	JOB START <u>4:45 AM</u>	JOB FINISH <u>5:30 AM</u>
LEASE <u>CROFFOTT</u> WELL # <u>A-10</u> LOCATION <u>Palco 2 E 2 S</u>				COUNTY <u>ROOKS</u> STATE <u>KANSAS</u>			
OLD OR <u>NEW</u> (Circle one)				<u>1/4 E 1/4 S INTO</u>			

CONTRACTOR A + A DRLG. Rig
 TYPE OF JOB PRODUCTION STRING
 HOLE SIZE 7 7/8 T.D. 3818'
 CASING SIZE 5 1/2 New DEPTH 3817'
 TUBING SIZE 14# CSG DEPTH
 DRILL PIPE DEPTH
 TOOL AFU INSERT DEPTH @ 3797'
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 21.55
 CEMENT LEFT IN CSG. 21.55
 PERFS.
 DISPLACEMENT 92.65 / BBL

OWNER
 CEMENT
 AMOUNT ORDERED 200SK ASC 2% GEL
10% SALT
500 GAL WFR-2 FLUSH

EQUIPMENT
 PUMP TRUCK CEMENTER Glenn
 # 398 HELPER GARY
 BULK TRUCK
 # 410 DRIVER BRANDON
 BULK TRUCK
 # DRIVER

COMMON	@		
POZMIX	@		
GEL	@	<u>4</u>	<u>164</u>
CHLORIDE	@		
ASC	@	<u>200</u>	<u>2620.00</u>
SALT	@	<u>19</u>	<u>364.80</u>
WFR-2	@	<u>500 gals</u>	<u>500.00</u>
HANDLING	@	<u>223</u>	<u>42370</u>
MILEAGE	@	<u>94/SK / MILE</u>	<u>1244.20</u>
TOTAL			<u>5179.30</u>

REMARKS:

PORT COLLAR ON # 52 JOINT (1648)
LAND PLUG @ 1200 #
FLOAT HELD
15 SK @ RAT HOLE

THANKS

CHARGE TO: TEN GASCO Inc.
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>164.00</u>
EXTRA FOOTAGE	@		
MILEAGE	@	<u>60</u>	<u>360.00</u>
MANIFOLD	@		
TOTAL			<u>1970.00</u>

Faxed

PLUG & FLOAT EQUIPMENT

Guide Shoe			<u>160.00</u>
AFU INSERT	@		<u>250.00</u>
S - CENTRALIZERS	@	<u>50.00</u>	<u>250.00</u>
T - BASKET	@		<u>150.00</u>
(B) PORT COLLAR	@		<u>1750.00</u>
TOTAL			<u>2560.00</u>

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Stacy Wagner

PRINTED NAME