

4-21

4-032053

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-179-21,075-00-00
SW NE SW /4 SEC. 05, 10 S, 26 W
1650 feet from S section line
3630 feet from E section line

Operator license# 9482 Lease Terry well # 1

Operator: National Petroleum Reserves County Sheridan 132.60

Address: 250 N. Rock Road Well total depth 4080 feet
Sutie #340 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67206 Surface pipe 8 5/8 Inch @ 251 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Blue Goose Drilling License# 5104

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 21 Month: April Year: 95

Plugging proposal received from: Leonard Steimetz

Company: Blue Goose Drilling Phone: _____

Were: Called at 12:00 midnight 04-20-95.
Order 190 sxs. 60/40 pozmix - 6% gel - 3% c.c.
Halliburton Cementing.
Conditon hole with heavy mud.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:30 P.M., Day: 21, Month: April, Year: 95

Actual plugging report: Spot cement plugs with drill pipe.
1st. plug at 2275' w/25 sxs.
2nd. plug at 1350' w/100 sxs.
3rd. plug at 300' w/40 sxs.
4th. plug at 40' w/10 sxs.
15 sxs. in rathole.
8 5/8" set at 251' w/155 sxs.

KANSAS CORPORATION COMMISSION
RECEIVED
05-01-1995
MAY 01 1995
CONSERVATION DIVISION
WICHITA, KS

Remarks: Halliburton Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES 2255 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2627 GL

I did[] / did not[] observe the plugging. Carl Goodrow

(agent)

INVOICED

DATE 5-5-95
INV. NO. 42762