

5-7

6 031360

API NUMBER 15- 179-20,961-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE NB SEC. 6, T 10 S, R 26 W 7E

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Lease Name Haffner Well # 1

Operator: National Pet. Reserves Inc.

County Sheridan 143.00

Name & Address 250 N. Rock Rd. #340

Well Total Depth 4400 feet

Wichita, Kansas 67206

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Emphasis License Number

Address Russell, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from John Collins

(company name) Emphasis (phone)

were: 8 5/8" set at 240' cwc. Circ hole with no less than 36 vis mud with no loss or gain. Balance plugs with mud and keep hole full.

Order 190 sks 60/40 poz 6% gel 3% cc. Halliburton Cement.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 1:00AM Day: 7 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2250 w/25 sks

1500' w/100 sks and hulls.

290' w/40 sks

40' w/10 sks

Circ. 15 sks in rathole.

05-30-1990

Remarks: 22238-10N - 80 Elev. 2622. Additional description is necessary, use BACK of this form.)

I (the STATE CORPORATION COMMISSION) did not observe this plugging.

DATE 6-5-90

Signed Carl Goodrow (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

Carl Goodrow