

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21229-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 8-28S-15W
330 feet from N Section Line, 1980 feet from E Section Line
Lease Name: DORGAN Well #: 1-8
County: PRATT Total Vertical Depth: 4654 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
CIBP		4637		
PROD	4.5	4653	2250	WITH 200 SX CMT
SURF	8.625	404		WITH 300 SX CMT

151.26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2008 10:15 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE DBA BRONCO ENERGY SERVICES
Proposal Rcvd. from: ANTHONY FARRAR Company: INDIAN OIL Phone: (620) 886-0373

Proposed Plugging Method: CIBP @ 4550' & 2 SX CMT. PLUG AT 980' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2008 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4550' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RUN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 980' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4647	4654		
4605	4611		


INVOICED
DATE 10-29-08
INV. NO. 2009060633

RECEIVED
OCT 14 2008
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Stephen J. Pfeifer
(TECHNICIAN)

[Handwritten signature]