

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21204-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 16-10S-26W
335 feet from S Section Line, 1373 feet from E Section Line
Lease Name: MARTIN 16D Well #: 1
County: SHERIDAN Total Vertical Depth: 4100 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 207

133.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/14/2008 3:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 08/14/2008 5:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs.
2nd. Plug at 1273' w/100 sxs.
3rd. Plug at 257' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

INVOICED
DATE 10-29-08
INV. NO. 2009060637

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 14 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Marvin Mills
(TECHNICIAN)

CM

Form CP-2/3

OCT 09 2008

PKT