

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19385-00-00
Spot: SESESE Sec/Twnshp/Rge: 2-10S-16W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: KRUSE UNIT Well #: 201
County: ROOKS Total Vertical Depth: 3205 feet

Operator License No.: 33993
Op Name: QUEST ENERGY LLC
Address: 2732 N REESE RD
BROOKVILLE, KS 67425

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3205	0	125 SX
SURF	7	196	0	50 SX

104.16

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2008 11:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: QUEST ENERGY LLC Phone: (785) 283-4249

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perfs: 1700' - 1160' - 250'.
PBTD 3185'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2008 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2945' - stacked out - pulled one joint out - spotted 75 sxs cement with 300# hulls.
Pulled tubing to 1840' - pumped cement until it circulated.
Well had good circulation at all times.
Braden head also was circulating - mixed 130 sxs cement with 100# hulls.
Pulled all tubing.
Hooked up to casing - pumped cement until it circulated out the braden head.
Mixed 75 to 80 sxs cement - had good cement to surface.

Perfs:

Top	Bot	Thru	Comments
3171	3180		
3156	3160		
3134	3147		
3113	3120		
3109	3111		
3094	3100		
3069	3080		

INVOICED
DATE 10/30/08
INV. NO 2009060654

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET 2#2262.

Plugged through: TBG

District: 04

Signed RyADinkel PIRT

(TECHNICIAN)

CM

Form CP-2/3

OCT 10 2008

PT