

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

CONFIDENTIAL ORIGINAL

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 5050
 Name: Hummon Corporation
 Address: 950 N. Tyler Road,
 City/State/Zip: Wichita, KS 67212-3240
 Purchaser: None
 Operator Contact Person: Brent B. Reinhardt
 Phone: (316) 773-2300
 Contractor: Name: Allen Drilling Company
 License: 5418
 Wellsite Geologist: Arden Ratzlaff

API No.: 15-007-22842 - 00 - 00
 County: Barber
 50'S & 50'W of 33
N2 SE SW Sec 4 Twp 33 S. Rng 15 East West
940 feet from S N (check one) Line of Section
1930 feet from E W (check one) Line of Section

RECEIVED
NOV 15 2004
KCC WICHITA
KCC

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

Footages Calculated from Nearest Outside Section Corner:
 (check one) NE SE NW SW
 Lease Name: Z-BAR Well #: 4-33
 Field Name: Platt South Field
 Producing Formation: Mississippian
 Elevation: Ground: 1670 Kelly Bushing: 1683
 Total Depth: 5000 Plug Back Total Depth: None

If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 _____ Deepening _____ Re-perf. _____ Conv. to Enhr./SWD
 _____ Plug Back _____ Plug Back Total Depth
 _____ Commingled _____ Docket No. _____
 _____ Dual Completion _____ Docket No. _____
 _____ Other (SWD or Enhr.?) _____ Docket No. _____
 _____ 8/6/04 _____ 8/16/04 _____ 9/12/04
 Spud Date or _____ Date Reached TD _____ Completion Date or
 Recompletion Date _____ Recompletion Date

Amount of Surface Pipe Set and Cemented at 801 Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set _____ Feet
 If Alternate II completion, cement circulated from _____
 feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan WHM 8-28-07
 (Data must be collected from the Reserve Pit)
 Chloride content 72000 ppm Fluid volume 900 bbls
 Dewatering method used Water Hauled
 Location of fluid disposal if hauled offsite:
 Operator Name: McGinness Oil Company
 Lease Name: LOHMANN SWDW License No.: 5255
 Quarter SE Sec. 3 Twp. 35 S. R. 12 East West
 County: Barber Docket No: D-4812


INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Brent B. Reinhardt
 Title: Production Manager Date: 11/12/04
 Subscribed and sworn to before me this 12th day of November,
 20 04
 Notary Public: Diana Salazar
 Date Commission Expires: Sept 3, 2008

KCC Office Use ONLY

Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 WIC Distribution



ORIGINAL

Side Two

Operator Name: Hummon Corporation Lease Name: Z-BAR Well #: #4-33

Sec 4 Twp 33 S. R. 15 East West County: Barber

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run (Submit- Copy)
List All E. Logs Run: LOG TECH: Dual Compensated Porosity;
Dual Induction; Microresistivity; Borehole Compensated Sonic Log;
Geological Report

CASING RECORD
Report all strings set-conductor, surface, intermediate, production, etc.
Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (in O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives.

ADDITIONAL CEMENTING / SQUEEZE RECORD
Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD - Bridge Plugs Set/Type
Specify Footage of Each Interval Perforated
Table with columns: Shots Per Foot, PERFORATION RECORD, Acid, Fracture, Shot, Cement Squeeze Record, Depth.

TUBING RECORD
Table with columns: Size, Set At, Packer At, Liner Run.

Producing Method
Table with columns: Date of First, Resumed Production, SWD or Enhr., Producing Method, Estimated Production Per 24 Hours, Oil Bbls., Gas Mcf, Water Bbls., Gas-Oil Ratio, Gravity.

Disposition of Gas
METHOD OF COMPLETION
Production Interval
Mississippian: 4770-4800'

**HUMMON CORPORATION
DAILY DRILLING REPORT
(ACO-1 Supplemental Page)**

**KCC
NOV 12 2004
CONFIDENTIAL**

Lease: Z Bar #4-33
Spot: N/2 SE SW
County: Barber
Contractor: Allen Drilling Co.
Geologist: Arden Ratzlaff
Mud Co.: Turbo Fluids
Gas Sniffer:
Testing:
Supply Co.: National Oilwell
Cement: Allied Cementing Co.
Key Well:

Prospect: Wildcat
Section: 33-33S-15W
State: Kansas

Elevation: G.L. 1670
 K.B. 1683

Spud Date: 8/6/04 @ 2:00am.

API # 15-007-22842-0000

| Tops | Sample | E-Log | | Key Well |
|---------------|--------|-------|------|----------|
| Indian Cave | | | | |
| Wabaunsee | 3094 | -1411 | 3054 | -1371 |
| Heebner | 3983 | -2300 | 3952 | -2269 |
| Lansing | 4194 | -2511 | 4151 | -2468 |
| Drum | 4429 | -2746 | 4390 | -2707 |
| Stark | 4551 | -2874 | 4514 | -2831 |
| Swope | | | | |
| Hush Puckney | | | | |
| Base of K.C. | 4638 | -2955 | 4594 | -2911 |
| Mississippian | 4815 | -3132 | 4762 | -3079 |
| Chattanooga | | | | |
| Viola | | | | |
| Total Depth | 5000 | -3317 | 4957 | -3274 |

8/6/04

MIRU. Spud at 2:00 a.m. Drilling at 0'-195'. Drilled 12 1/4" hole. Ran 8 5/8" surface casing set at 801' with 375 sacks of cement, 3% calcium chloride, 2% gel. Cement 1" down from top and circulated wait on cement for 8 hours.

No DRILL STEM TEST were taken.

**RECEIVED
NOV 15 2004
KCC WICHITA**

ALLIED CEMENTING CO., INC. 18178

Federal Tax I.C. # 4

REMIT TO P.O. BOX 51
RUSSELL, KANSAS 67665

SERVICE POINT:
MEDICINE LODGE

| | | | | | | | |
|-------------------------|-----------------------------------|------------------------------------|----------------------|-----------------------------|----------------------------|--------------------------|---------------------------|
| DATE <u>8-7-04</u> | SEC. <u>33</u> | TWP. <u>33s</u> | RANGE <u>15w</u> | CALL RD. OUT <u>7:30 PM</u> | ON LOCATION <u>9:30 PM</u> | JOB START <u>2:15 AM</u> | JOB FINISH <u>7:00 AM</u> |
| BASE <u>Z-BAR</u> | WELL # <u>4-33</u> | LOCATION <u>160' DEERHEAD ROAD</u> | COUNTY <u>BARBER</u> | STATE <u>KANSAS</u> | | | |
| OLD OR NEW (Circle one) | <u>11.3 S, E THRU C.C., 1/2 S</u> | | | | | | |

CONTRACTOR ALLEN #5 OWNER HUMMON CORP.
 TYPE OF JOB SURFACE CASING
 HOLE SIZE 8 1/4" ID 800'
 CASING SIZE 8 1/8" X 3/4" DEPTH 800'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 30.80'
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 4 1/2 BBL WATER
 EQUIPMENT _____

CEMENT
 AMOUNT ORDERED 175 SY CLASS A + 3% CCL
275 SY 65:35:6 + 3% CCL + 1/4" FIN SEAL
100 SY CLASS A + 3% CCL + 2% BCL
 COMMON A 100 @ 7.85 785.00
 POZMIX _____ @ _____
 GEL _____ @ 11.00 22.00
 CHLORIDE 14 @ 33.00 462.00
 ASC _____ @ _____
NEW 275 @ 7.30 2007.50
FIN SEAL 64# @ 1.40 96.60
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING 589 @ 1.35 795.15
 MILEAGE 589 X 3.0 1767.00
 TOTAL 6623.50

PUMP TRUCK CEMENTER KEVIN BROWARD
 # 368-265 HELPER BILL MCDONN
 BULK TRUCK
 # 359-251 DRIVER JARVIS REEVES
 BULK TRUCK
 # 364 DRIVER LOREN G. TRAMER

REMARKS:

RUN 8 1/8" C.S. + BROAD CEMENTATION
PUMP 5 BBL FRESH WATER
MIX 275 SY CLASS A + 3% CCL + 1/4" FIN
SEAL WITH 100 SY CLASS A + 3% CCL + 2% BCL
DISPLACE PUG TO 789' / BBL WATER
CEMENT DID NOT CURRYATE!
CURRYATE CEMENT TO SURFACE THRU
1" WITH 175 SY A + 3% CCL

SERVICE

DEPTH OF JOB 800'
 PUMP TRUCK CHARGE 0-300' 590.00
 EXTRA FOOTAGE 500' @ .50 250.00
 MILEAGE 30 @ 4.00 120.00
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL 940.00

PLUG & FLOAT EQUIPMENT

1- 8 1/8" TRP @ 100.00 100.00
1- Baffle Plate @ 45.00 45.00
1- CENTRALIZER @ 55.00 55.00
1- BASKET @ 130.00 130.00
 _____ @ _____

TOTAL 380.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE 7943.50
 DISCOUNT 794.35 IF PAID IN 30 DAYS

SIGNATURE

Miles Smith

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

Miles Smith
PRINTED NAME

KCC
 NOV 12 2004
 CONFIDENTIAL

ALLIED CEMENTING CO., INC. 17601

Federal Tax I.D. _____

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

| | | | | | | | |
|------------------------------------|-------------------|---------------------------------------|------------------|---------------------------|----------------------------|-------------------------|--------------------------|
| DATE <u>8-17-04</u> | SEC <u>33</u> | TWP <u>33S</u> | RANGE <u>15W</u> | CALLLED OUT <u>3:30AM</u> | ON LOCATION <u>10:00AM</u> | JOB START <u>7:20PM</u> | JOB FINISH <u>8:20PM</u> |
| LEASE <u>Z-Box</u> | WELL# <u>4-23</u> | LOCATION <u>1/2 & Deerhead RD</u> | | | COUNTY <u>Barber</u> | STATE <u>Ks</u> | |
| OLD OR NEW (Circle one) <u>NEW</u> | | LOCATION <u>1 1/2 S E 1/4 T 30</u> | | | | | |

CONTRACTOR Allen #15 OWNER Humman Corp.
 TYPE OF JOB Long String
 HOLE SIZE 7 7/8 TD 4957
 CASING SIZE 4 1/2 DEPTH 4961
 TURING SIZE DEPTH
 DRILL PIPE 4 1/2 DEPTH 4957
 TOOL DEPTH
 PRES. MAX 900 PSI MINIMUM 160 PSI
 MEAS. LINE SHOE JOINT 33.57
 CEMENT LEFT IN CSG. 33.57 FT
 PERFS.
 DISPLACEMENT Kal Water 20 BBLs
 EQUIPMENT

CEMENT
 AMOUNT ORDERED 325 SA # + 10% Cys
10% Salt 6 # 140 - Seal 89% FPM 60
1/4 # Floss Seal
 COMMON 325 "H" @ 9.55 3103.75
 POZMIX @
 GEL @
 CHLORIDE @
 ASC @
 Gyp Seal 31 @ 17.85 553.35
 SALT 35 @ 7.50 262.50
 KOL SEAL 1950 # @ .50 975.00
 FK-160 244 # @ 8.00 1952.00
 Floss Seal 31 # @ 1.40 113.40

PUMP TRUCK CEMENTER David W.
 # 352 HELPER Tracy C.
 BULK TRUCK
 # 351a DRIVER Chris R.
 BULK TRUCK
 # DRIVER

HANDLING 438 @ 1.35 591.30
 MILEAGE 30 X 438 X .05 1652.00
 TOTAL 8208.30

REMARKS:

P.D. on Bottom Breakline for
2 1/2 hr Pump 12 BBLs Mud Clean
Pump 2 hrs H.F. 10% Cys 10%
Salt 10% KOL Seal 10% Floss 1/4
Floss Seal 3 hr David Wash PUMP
& Line Displacement Kal Water slow
Rate Pump Plug Float 2000
128 FT in a.m.

SERVICE

DEPTH OF JOB 4961
 PUMP TRUCK CHARGE 1315.00
 EXTRA FOOTAGE @
 MILEAGE 30 @ 4.00 120.00
 @
 @
 @

CHARGE TO: Humman Corp.
 STREET _____
 CITY _____ STATE _____ ZIP _____

TOTAL 1435.00

PLUG & FLOAT EQUIPMENT

MANIFOLD @
1 1/2 inch Down Pipe @ 300.00 300.00
1 1/2 AF4 Float Shoe @ 200.00 200.00
5 1/2 inch Float Shoe @ 55.00 275.00
 TOTAL 775.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment
 and furnish cementer and helper to assist owner or
 contractor to do work as is listed. The above work was
 done to satisfaction and supervision of owner agent or
 contractor. I have read & understand the "TERMS AND
 CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE 10418.30
 DISCOUNT 1041.83 IF PAID IN 30 DAYS

SIGNATURE [Signature] ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING
 PRINTED NAME William R. Mouser

KCC
 NOV 12 2004
 CONFIDENTIAL

RECEIVED
 NOV 15 2004
 KCC WICHITA