

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 175-22154-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date Spud 10-11-08, Compl 10-20-08

Well Operator: Cabot Oil & Gas Corporation KCC License #: 6120
(Owner / Company Name) (Operator's)

Address: 600 17th Street, Ste. 900N City: Denver

State: Colorado Zip Code: 80202 Contact Phone: (303) 226-9443

Lease: Strickland Well #: 1-30 Sec. 30 Twp. 33 S. R. 33 East West

SE - SE - NE Spot Location / QQQQ County: Seward

2,310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 55' Cemented with: 9 yards Ready Mix Sacks

Surface Casing Size: 8-5/8" Set at: 1,528' Cemented with: 820 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: 2,859' (G.L. / K.B.) T.D.: 6,500' PBTD: 0' Anhydrite Depth: Approx. 1,605'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 50 sacks 60:40:4 from 1,560' up, 50 sacks 60:40:4 from 540' up, 20 sacks 64:40:4 from 60' up, 15 sks in rat hole, 10 sks in mouse hole. Above plugging procedure verbally approved by Jerry Stapleton of the KCC 10-20-08.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs will be filed with ACO-1. No ACO-1 filed due to work not being completed.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jim Leonard - Contract Engineer

Phone: (303) 226-9400 Ext. 146

Address: 600 17th Street, Ste. 900N City / State: Denver, CO 80202

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: Box 368, 281 & River Road, Medicine Lodge, KS 67104 Phone: (620) 886-5926

Proposed Date and Hour of Plugging (if known?): October 20, 2008 7:45 PM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 10-20-08 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2008

CONSERVATION DIVISION,
WICHITA, KS
Dist 1

*Well Plugged KCC-PKT

PKT