

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 155-20,600-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_

Well Operator: Zenith Drilling Corporation KCC License #: 5141  
(Owner / Company Name) (Operator's)

Address: P. O. Box 780428 City: Wichita

State: Kansas Zip Code: 67278-0428 Contact Phone: ( 316 ) 684 - 9777

Lease: Key Well #: 1 Sec. 6 Twp. 22 S. R. 9  East  West

- SW - SW - NW Spot Location / QQQQ County: Reno

2970 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 4950 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 ENHR Docket # E-27558  Other: KCC Pkt Pen Lic

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 217' Cemented with: 225 Sacks

Production Casing Size: 5-1/2" Set at: 3620 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf. @ 3554 to 3558

Elevation: 1747 ( G.L. /  K.B.) T.D.: 3720' PBDT: 3584' Anhydrite Depth: 320'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): To be plugged in accordance with the rules & regulations of the KCC

RECEIVED  
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

OCT 28 2008

If not explain why? \_\_\_\_\_

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Chuck Schmidt Phone: ( 316 ) 755 - 3523

Address: 1321 West 93rd North City / State: Valley Center, Ks. 67147

Plugging Contractor: Mike Kelso KCC License #: 31529  
(Company Name) (Contractor's)

Address: P. O. Box 467, Chase, KS. 67524-0467 Phone: ( 620 ) 938 - 2943

Proposed Date and Hour of Plugging (if known?): As soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-27-08 Authorized Operator / Agent: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dust 2  
PKT

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - KEY #1  
Located: SW/4 SW/4 NW/4, Section 6-22S-9W, Reno County,  
Kansas

OWNER: Equitx Energy Corporation  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 14, 1979  
COMPLETED: August 21, 1979

TOTAL DEPTH: 3720'

LOG

0 - 320 Sand - Shale  
320 - 735 Shale, Red Bed  
735 - 935 Shale  
935 - 1130 Salt  
1130 - 2900 Lime and Shale  
2900 - 3720 Lime

CASING RECORD

Ran 6 joints 8 5/8" OD casing, 206.84'  
cemented at 217' K.B. with 225 sacks  
Class H with 2% gel and 3% cc. Plug  
down at 12:00 Mignight, 8-14-79, by  
Dowell.

Ran 91 joints 5 1/2" OD casing, 3621'  
14# new casing set at 3620' K.B. with  
200 sacks RFC cement, 10# Kolite per  
sack. Plug down at 9:45 PM, 8-21-79,  
by Dowell.

Deviation Surveys: 1/2° at 1620'  
3/4° at 3700'

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 28 2008

CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

ZENITH DRILLING CORPORATION  
PO BOX 780428  
WICHITA, KS 67278-0428

November 03, 2008

Re: KEY #1  
API 15-155-20600-00-00  
6-22S-9W, 2970 FSL 4950 FEL  
RENO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after May 2, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000