

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 173-20997-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 08-18-08

Well Operator: James B. Ash d/b/a Jaguar Oil & Gas KCC License #: 33398
(Owner / Company Name) (Operator's)

Address: 201 Susan Lane City: Andover

State: Kansas Zip Code: 67002 Contact Phone: (316) 733 - 8684

Lease: George/GWA Well #: 1 Sec. 35 Twp. 25 S. R. 1 East West

C - NW - SE - NE Spot Location / QQQQ County: Sedgwick

1650 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 216 Cemented with: 150 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1385/1389 (G.L. / K.B.) T.D.: 3422 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Use 60/40 poz cement with no more than 4% gel. **RECEIVED**
35 sx at 2180', 35 sx at 265', 25 sx at 60' circulate to surface. 15 sx in rathole. **KANSAS CORPORATION COMMISSION**

OCT 29 2008

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

**CONSERVATION DIVISION
WICHITA, KS**

If not explain why? Finalized geological report has not yet been received from the site geologist as requested by Jaguar Oil & Gas on numerous occasions.

The ACO-1 form will be filed upon receipt of final geological report and within the 120 day deadline.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: James B. Ash

Phone: (316) 733 - 8684

Address: 201 Susan Lane City / State: Andover, KS 67002

Plugging Contractor: Paul Carageannis d/b/a AA Drilling KCC License #: 32753
(Company Name) (Contractor's)

Address: P.O. Box 771189, Wichita, KS 67277 Phone: (316) 832 - 0988

Proposed Date and Hour of Plugging (if known?): 11:00 AM
12:00 p.m. on 08-29-08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-28-08 Authorized Operator / Agent: James B. Ash (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 2

PKT

**Well plugged - KCC - PKT*

WELL LOG

James B. Ash d/b/a Jaguar Oil & Gas
#1 GEORGE/GWA
C NW SE NE
Section 35-T25S-R1E

Elevation 1389 KB

Formation (Top), Depth and Datum		(Sample)
Name	Top	Datum
Brown Lime	2191	(-802)
Kansas City	2532	(-1143)
Base Kansas City	2704	(-1315)
Mississippian	3004	(-1615)
Hunton	3416	(-2027)
Total Depth	3422	(-2033)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 29 2008

CONSERVATION DIVISION
WICHITA, KS