

Amended

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 095-21622 - 00-00 (identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11/7/89

Well Operator: McCoy Petroleum Corporation (Owner / Company Name) KCC License #: 5003 (Operator's)

Address: 8080 E. Central, Suite #300 City: Wichita

State: KS Zip Code: 67206-2366 Contact Phone: 316-636-2737

Lease & Well #: KYLE, H.C. #3-3 Sec. 3 Twp. 30s Rng. 7  East  West

Spot Location / Qtr Secs County: Kingman

810 Feet (in exact footage) From  North  South (from nearest outside section corner) Line of Section (Not Lease Line)  
1825 Feet (in exact footage) From  East  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket #  ENHR Docket #  Other:

Conductor Casing Size: None Set at: None Cemented with: None Sacks

Surface Casing Size: 8 5/8" Set at: 289' Cemented with: 170 Sacks

Production Casing Size: 5 1/2" Set at: 4208' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4143-4153'. Squeeze from 2709-2740 on 2/16/07. Resqueeze with 25 sks cement on 6/11/07.

Elevation: 1496  G.L.  K.B. T.D. 4210' PBDT: 4159' Anhydrite Depth: NA (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole Top Of Production String Cement: NA

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand to 4080' & 5 sacks cement, Recover Pipe, Pull to 1100' and spot 35 sacks cement. Pull to 700' and spot 35 sacks cement. Pull to 340' and circulate cement to surface.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Logs have already been filed with the KCC with the original ACO-1 filing.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et.seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Scott Hampel

McCoy Petroleum Corporation Phone: 316-636-2737

Address: 8080 E. Central, Suite #300 City / State: Wichita, KS 67206-2366

Plugging Contractor: Quality Well Service (Company Name) KCC License #: 31925 (Contractor's)

Address: 190th US 56 Highway, Ellinwood, KS 67526 Phone: 620-727-3410

Proposed Date and Hour of Plugging (if known?): ASAP - Plugging Orders from Jeff Klock - KCC

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/27/08 Authorized Operator / Agent: Scott Hampel (Signature)

*Scott Hampel*  
Scott Hampel

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 28 2008  
CONSERVATION DIVISION  
WICHITA, KS