

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32834  
Name: JTC Oil, Inc.  
Address: P.O. Box 910  
City/State/Zip: Louisburg, KS 66053  
Purchaser: CMT Transportation, Inc.  
Operator Contact Person: Tom Cain  
Phone: (913) 208-7914  
Contractor: Name: Town Oil Company  
License: 6142

Wellsite Geologist: \_\_\_\_\_  
Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)  Docket No. \_\_\_\_\_  
7-28-06 7-31-06 8-17-06  
Spud Date or Date Reached TD Completion Date or  
Recompletion Date Recompletion Date

API No. 15 - 059-25,150-00-00  
County: Franklin  
NW NW NE NW Sec. 32 Twp. 15 S. R. 21  East  West  
5060 feet from (S) / N (circle one) Line of Section  
3850 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Moldenhauer Well #: W-7  
Field Name: Paola-Rantoul  
Producing Formation: Squirrel  
Elevation: Ground: \_\_\_\_\_ Kelly Bushing: \_\_\_\_\_  
Total Depth: 802' Plug Back Total Depth: \_\_\_\_\_  
Amount of Surface Pipe Set and Cemented at 21' Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from 21'  
feet depth to 0 w/ 5 sx cmt.

Drilling Fluid Management Plan alt. II RGR 10/29/07  
(Data must be collected from the Reserve Pit)  
Chloride content 1500-3000 ppm Fluid volume 80 bbls  
Dewatering method used used on lease  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]  
Title: Pres. Date: 11-28-06  
Subscribed and sworn to before me this 28 day of November  
20 06.  
Notary Public: [Signature]  
Date Commission Expires: 10/29/2010

**KCC Office Use ONLY**

Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received

**RECEIVED**  
**DEC 04 2006**

**TERRY'S GRATWICK**  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 10/29/2010 KCC WICHITA



TDR Construction, Inc.

913-710-5400

Louisburg, KS

Well: Moldenhauer # W-7

Thickness of Strata

Well Log

Formation

Total Depth

Thickness of Strata	Formation	Total Depth
0	Soil	10
9	Clay	19
49	Shale	68
3	Lime	71
4	Shale	75
17	Lime	92
9	Shale	101
10	Lime	111
3	Shale	114
19	Lime	133
38	Shale	171
20	Lime	191
79	Shale	270
24	Lime	294
1	Coal	295
11	Shale	306
6	Lime	312
20	Shale	332
1	Lime	333
22	Shale	355
2	Lime	357
15	Shale	372
26	Lime	398
9	Shale/Slate	407
20	Lime	427
4	Shale	431
4	Lime	435
4	Shale	439
5	Lime	444
176	Shale	620
6	Lime	626
21	Shale	647
5	Lime	652
16	Shale	668
4	Lime	672
12	Shale	684
7	Lime	691
14	Shale	705
5	Lime	710
7	Shale	717
3	Oil Sand	720
3	Lime	723
12	Oil Sand	735
7	Sand	742
60	Shale	802

TD 802 RECEIVED

DEC 04 2006

KCC WICHITA

CONSOLIDATED OIL WELL SERVICES, INC.  
 P.O. BOX 884, CHANUTE, KS 66720  
 620-431-9210 OR 800-467-8676

TICKET NUMBER 08798  
 LOCATION 07 Aug  
 FOREMAN Alan Madec

TREATMENT REPORT & FIELD TICKET  
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-1-06	4015	Mildenbauer # W-7	32	15	21	Jn
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
JTC			396	Al Madec		
MAILING ADDRESS			164	Ric Arb		
P.O. Box 910			122	Ken Han		
CITY	STATE	ZIP CODE				
Louisburg	KS	66053				

JOB TYPE long string HOLE SIZE 5 7/8 HOLE DEPTH 800 CASING SIZE & WEIGHT 2 7/8  
 CASING DEPTH 786 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Established rate. Mixed + pumped 200 # gel followed by 5 bbl water. Mixed + pumped 98 6x 50/50 doz, 5 # Kol-seal, 5% salt, 2% gel, 1/4 # flo-seal. Circulated cement to surface. Flushed pump clean. Pumped 2 1/2 rubber plug to pin @ 786. Well held 800 PSI for 30 min MFT. Closed valve.

Customer supplied water

Alan Madec

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	164	800.00
510B	0	MILEAGE on location	164	0
5402	786'	Casing footage	164	MTC
5407A	1/2 of min	second well	122	137.50
1107	25 #	flo-seal		45.00
110A	490 #	Kol-seal		176.40
1111	245 #	salt		71.05
1118B	396 #	gel		55.46
1124	875x	50/50 doz		769.9
5402	1	2 1/2 plug		20.00
			RECEIVED	
			DEC 04 2006	2073.3
			KCC WICHITA	
			6.8%	
			SALES TAX	77.38
			ESTIMATED TOTAL	2152.72

AUTHORIZATION \_\_\_\_\_

TITLE Well # 207820

DATE Alan Madec