

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mikelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mikelson guarantees payment of the plugging fee.

Operator's full Name: Executive Petroleum Company,

Complete Address: 1007 Denver U. S. National Center, Denver, Colorado.

Lease Name: McGuire Well No. 1

Location: S/2-NW-NE Sec. 7 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4030 Oil Well ---

Gas Well --- Input Well --- SWD Well --- D & A X Lost Hole ---

Mr. Mikelson was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1280' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

CP-2

H. L. Nichols
Conservation Division Agent