



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Co., has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Kimbark Operating Company.

Complete Address: 288 Clayton St., Denver, Colorado.

Lease Name: William Well No. 1

Location: NE-NW-SE Sec. 7 Twp. 10 Rge. (E)(W)25

County Graham Total Depth 4050 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

186'--8 5/8" Surface pipe, cement circulated with 165 Sx. Dakota section from 1740' to 1922'

Circulate hole with heavy mud, pull DP to 1950' and displace 100 Sx. cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP. Pull DP. Set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent