

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Baalman Well No. B-1

Location: SW-SW-NW Sec. 12 Twp. 10 Rge. (E)(W) 30

County: Sheridan Total Depth 4265' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

233'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent