

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Earl Dunlap of C & G Drilling Co., has this

date requested permission to plug the following described well:

D. G. Hansen
Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Knoll Well No. A-1

Location: SW-SW-SW Sec. 13 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 3976 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

184' - 8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

" " 175' with 1/4 sk hulls & 20 Sx. cement.

" " 40' with 1/2 sk hulls & 10 Sx. cement.

Very truly yours,

H. D. Nichols
Conservation Division Agent