



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt Oil Operations,

Complete Address: Drawer #370, Hays, Kansas,

Lease Name: Alice Knoll Well No. 1

Location: SW-SE-NE Sec. 13 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 3744' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

154'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1190' and displace 100 Sx.
cement thru DP. Pull DP to 185' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent