

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 7 1963

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this

date requested permission to plug the following described well:

Texaco Inc.,

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Texaco Incorporated,

Complete Address: 614 Bitting Building, Wichita, Kansas.

Lease Name: A. M. Knoll Well No. 1

Location: GSE-SW Sec. 26 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4409 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

258' -- 9 5/8" surface pipe, cement circulated w/165 Sx.  
4090' 4 1/2" casing cemented w/125 Sx. Top plug back @ 2525'  
Top perforation @ 2493', pumped in 50 Sx cement.

Sand well back to 2480' and set 4 Sx cement w/ dump bailer.  
Pull casing to 550', circulate heavy gel mud and displace 20  
Sx cement thru 4 1/2". Pull casing to 240', and displace 20 Sx  
cement thru 4 1/2". Pull casing, set bridge @ 40' and 10 Sx  
cement to bottom of cellar.

Very truly yours,

H. L. Nichols  
 Conservation Division Agent