

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 8 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Knoll Well No. A-1

Location: CSW-SE Sec. 26 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4040 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. L. Nichols*  
 Conservation Division Agent