

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: 200 West Douglas, Wichita, Kansas.

Lease Name: Knoll Well No. 1

Location: SW-NE-SE Sec. 26 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent