


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 12 Twp. 10S Rge. (E) 25 (W)  
Location as "NE/CNW/SW" or footage from lines NW SW NW  
Lease Owner Kimbark Exploration Company  
Lease Name Herman Well No. 1  
Office Address 201 University Blvd. - Denver 6, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2/28 19 62  
Application for plugging filed 3/6 19 62  
Application for plugging approved 3/6 19 62  
Plugging commenced 2/28 19 62  
Plugging completed 2/28 19 62  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation None Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	195'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud T.D. -3975-210'  
20 sacks cement 185-100'  
10 sacks cement 30'-0'

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
03-22-62


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kimbark Exploration Company  
Address Same

STATE OF Colorado, COUNTY OF Denver, ss.  
W. K. Arbuckle, President (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. K. Arbuckle  
201 Univ. Blvd. - Denver  
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of March, 1962



Notary Public

HERMAN #1 WELL

Location: NW SW NW Section 12  
T-10-S, R-25-W  
Graham County, Kansas

Spudded: 2/17/62  
Completed: 2/28/62

KB: 2474

Owner: Kimbark Exploration Company  
201 University Blvd.  
Denver 6, Colorado

Contractor: Kimbark Exploration Co.  
201 University Blvd.  
Denver 6, Colorado

Surface Casing: 8 5/8" ss casing cemented at 205' K.B. with 165 sxs quick set.

Oil String: None

LOG

Figures indicate bottom of formation--

110	Sand-Shale
825	Shale
1,375	Shale, Sand
1,650	Shale
2,340	Shale & Shells
2,500	Shale-Lime
2,945	Shale-Lime
3,135	Lime
3,415	Lime
3,666	Lime
3,772	Lime
3,843	Lime
3,928	Lime
3,975	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1962  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, W. K. Arbuckle, President of Kimbark Exploration, hereby certifies that the above is a true and correct log of the formations encountered in drilling the Herman #1 as shown in the daily drilling reports.

KIMBARK EXPLORATION COMPANY

*W. K. Arbuckle*

W. K. Arbuckle, President

STATE OF COLORADO ) ss  
CITY & COUNTY OF DENVER)

Be it remembered that on this 6th day of March A.D. 1962, before me, Marilyn A. Rehm, a Notary Public, personally appeared W. K. Arbuckle, President of Kimbark Exploration Company a Colorado Corporation, who is personally known to me and known to me to be the President of said Corporation, and the same person who executed the foregoing instrument, and he duly acknowledged the execution of the same for and on behalf of and as the act and deed of said Corporation.

WITNESS my hand and official seal:

My Commission Expires November 15, 1964

*Marilyn A. Rehm*  
Notary Public

