

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,458-00-00

LEASE NAME Knoll

WELL NUMBER #1

3960 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 26 TWP. 10S RGE. 25W (E) or (W)

COUNTY Graham

Date Well Completed 5-18-88

Plugging Commenced 8:20 a.m.

Plugging Completed 10:30 a.m.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Geana Oil Company

ADDRESS Route 1, Box 4

PHONE# (913) 743-5419 OPERATORS LICENSE NO. 7013

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 17, 1988 (date)

by Marion Schmitt (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

SEP 22 1988 09-22-88

Formation	Content	From	To	Size	Put in	Produced out
Fresh Water Zones	Sand & Shale	0	226	8 5/8 2#	5-11-88	Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. The hole was filled with drilling fluid from TD to 2210'. 25 sks cement were placed at 2210'. Drilling mud was placed from 2210' to 1270'. 100 sks cement were placed at 1270' with 1 sk of celloflake. Hole was filled with drilling fluid from 1270' to 230'. 40 sks of cement were placed 230'. Hole filled with drilling fluid to 40'. 10 sks of cement at 40'. 15 sks in rathole, 10 sks (If additional description is necessary, use BACK of this form.) (on back)

Name of Plugging Contractor Lloyd Drilling Company License No. 3300

Address St. Peter Route, Morland, Kansas 67650


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GEANA OIL COMPANY

STATE OF Kansas COUNTY OF Trego, ss.

Charles R. Rhoades (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles R. Rhoades

(Address) RT#1, Box 4, WAKEENEY, KS 67672



SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 88
Charlotte Wanker
Notary Public

My Commission Expires: May 16, 1992

of cement in mousehole. A total of 200 sks of 60/40 poz, 3% CC, 6% gel
with 1 sk of hulls was sued.

88-53-85

WALKER