

15-065-20135-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 26 Twp. 10S Rge. (E) 25 (W)

Location as "NE/CNW%SW%" or footage from lines C SW SE

Lease Owner Chief Drilling Co., Inc.

Lease Name KNOLL "A" Well No. 1

Office Address Box 797 - Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4/4 19 68

Application for plugging filed 4/4 19 68

Application for plugging approved 4/4 19 68

Plugging commenced 4/4 19 68

Plugging completed 4/4 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4040 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	210	8-5/8"	210	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 1200'
Mixed 70 sacks cement through drill pipe
Wooden plug set @ 215'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Box 797 - Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Thomas G. Wesselowski (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Thomas G. Wesselowski

Box 797 - Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 1968

Carmen R. Cook
Carmen R. Cook
Notary Public.



15-065-20135-00-00

RECEIVED
CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

KNOLL "A" #1
C SW SE Sec. 26-10S-25W
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 3-28-68
Completed: 4-4-68

Casing Record: 8-5/8" @ 210' w/160 sacks 60/40 Pozmix, 2% Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			2473 Gr.
			2475 D.F.
			2478 K.B.
			<u>LOG TOPS</u>
Surface Sand & Clay	0	140	Anhydrite (driller) 2130 + 348
Shale & Sand Streaks	140	940	Heebner 3758 -1280
Shale w/Shells & Sand	940	1285	Toronto 3782 -1304
Shale & Sand	1285	1705	Lansing 3798 -1320
Sand	1705	1900	Base Kansas City 4032 -1554
Shale	1900	1950	Log Total Depth 4039 -1561
Shale, Red Bed and Sand Streaks	1950	2130	
Anhydrite	2130	2170	
Shale & Shells	2170	2695	
Lime & Shale	2695	3837	
Lime	3837	3840	
Lime & Chert	3840	3900	
Lime	3900	4040	
Total Depth	4040		

STATE OF KANSAS, COUNTY OF BARTON) SS


I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW SE Section 26-10S-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Thomas G. Wesselowski
Thomas G. Wesselowski, Geologist

Subscribed and sworn to before me this 5th day of April, 1968.

Carmen R. Cook
Carmen R. Cook, Notary Public



My commission expires: Dec. 12, 1970.