

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00810-00-00
Spot: SESWNW Sec/Twnshp/Rge: 36-30S-9W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SWINGLE "A" Well #: 3
County: KINGMAN Total Vertical Depth: 4449 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4448	2600	110 SX
SURF	8.625	249		165 SX

144.59

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/17/2008 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUAILTY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND PERFS BACK TO 4350' CAP WITH 4 SKS CMT. REC. CASING. SPOT 35 SKS 1450', 35 SKS 950', CIRC CMT FROM 300'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 09/17/2008 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE NOTCH WAS COVERED WITH SAND TO 4350' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2600' AND PULLED TO 1450', WHERE 35 SKS OF CMT WAS SPOTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4404			

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-20-08
INV. NO. 2009060549

Remarks: QUALITY OIL WELL CEMENTING #2224 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____
(TECHNICIAN)