

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20923-00-00
Spot: NESE Sec/Twnshp/Rge: 11-25S-2E
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: ENTZ Well #: 2
County: SEDGWICK Total Vertical Depth: 2852 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2847	1850	100 SKS.
SURF	8.625	200		120 SKS. <u>92.69</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SAND TO 2730' AND CAP W/5 SXS CEMENT. CIRCULATE TO SURFACE FROM 250'.

Plugging Proposal Received By: DAVE WERTZ Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 4:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2730' AND CAPPED WITH 5 SXS CEMENT. CUT AND PULLED PIPE TO 250'. CIRCULATED 100 SXS CEMENT FROM 250' TO SURFACE.

INVOICED
DATE 10-20-08
INV. NO. 2009060551

Perfs:

Top	Bot	Thru	Comments
2780	2788		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE TOTAL = 100 SXS 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed Meg Eves
(TECHNICIAN)

PEV