

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23242-00-01
Spot: N2S2SE Sec/Twnshp/Rge: 20-30S-5E
1099 feet from S Section Line, 1387 feet from E Section Line
Lease Name: MEANS A Well #: 2
County: COWLEY Total Vertical Depth: 2975 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2889		PACKER TYPE AND SETTING DEPTH: AD-1 SET @ 2889'
PROD	4.5	2961	1640	150
SURF	8.625	207		290 SX
T1	2.375	2889		96.69

Well Type: SWD UIC Docket No: E28109.1 Date/Time to Plug: 08/14/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/14/2008 5:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2880', DUMP BAILED 4 SXS CEMENT ON TOP. CUT 4-1/2" CASING @ 1690', LAYED DOWN 1440' 4-1/2" CASING. W/4-1/2" CASING @ 250', QUALITY WELL SERVICE MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 4-1/2" CASING. CEMENT CIRCULATED. PLUG DOWN 5:30 P.M., 8-4-2008. QUALITY CEMENT TICKET #2213.

Perfs:

Top	Bot	Thru	Comments
2938	2975		
INVOICED			
DATE <u>10-20-08</u>			
INV. NO. <u>2009060552</u>			
RECEIVED KANSAS CORPORATION COMMISSION			
SEP 26 2008			
CONSERVATION DIVISION WICHITA, KS			

Remarks: E-28109

Plugged through: CSG

District: 02

Signed: *Duane Krueger*
(TECHNICIAN)

PKT