

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20010-00-01
Spot: SWNWNE Sec/Twnshp/Rge: 33-30S-9W
1010 feet from N Section Line, 2195 feet from E Section Line
Lease Name: WESTERMAN Well #: 1 OWWO
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4884	2180	50 SX
SURF	8.625	249		200 SX <u>146.25</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/15/2008 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND THE PERFS BACK 50' ABOVE THE TOP PERF. CAP WITH 4 SKS CMT. RECOVER CASING, 35 SKS 1500', 35 SKS 950', CIRC CMT FROM 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/15/2008 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4260', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2180', AND PULLED TO 1500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4311	4328		

INVOICED
DATE 10-20-08
INV. NO. 2009060553

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL CMTG 2223 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)