

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25778-00-00  
Spot: NWNW Sec/Twnshp/Rge: 10-11S-16W  
630 feet from N Section Line, 660 feet from W Section Line  
Lease Name: ROGER Well #: 10-2  
County: ELLIS Total Vertical Depth: 3669 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 9915 W 21ST ST, STE B  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		150 SX COMMON CMT 3% CC, 2% GEL

119.24

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2008 12:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2379

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 07/11/2008 1:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3614' w/25 sxs.  
2nd. Plug at 1150' w/25 sxs.  
3rd. Plug at 650' w/60 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 10-21-08  
INV. NO. 2009060563

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 25 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris  
(TECHNICIAN)

SEP 24 2008

PKY