

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29754-00-00
Spot: SWSWSESW Sec/Twnshp/Rge: 21-23S-20E
220 feet from S Section Line, 3740 feet from E Section Line
Lease Name: NILGES Well #: 1
County: ALLEN Total Vertical Depth: 1000 feet

Operator License No.: 30993
Op Name: M.A.E. RESOURCES, INC.
Address: PO BOX 304
PARKER, KS 66072

String Size Depth (ft) Pulled (ft) Comment
SURF 6.625 24 0

35.00

Well Type: OH DH KCC PRT UIC Docket No: _____ Date/Time to Plug: 07/10/2008 9:30 AM

Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: BRAD COOK Company: MAE RECOURCES, INC. Phone: (620) 852-3333

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1000'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 1000', A 50' CEMENT PLUG AT 550', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: RUSSELL HINE
Date/Time Plugging Completed: 07/10/2008 12:00 AM

Witness Type: NONE
KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

PIPE WAS RAN INTO THE WELL TO 1000'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 1000'. THE PIPE WAS PULLED TO 550' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

SEP 17 2008 CPT
CHANUTE, KS

INVOICED
DATE 10-21-08
INV. NO. 2009060566

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

SEP 29 2008 CP-2/3
CONSERVATION DIVISION
WICHITA, KS

PRT