

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-26282-00-00  
Spot: NESW Sec/Twnshp/Rge: 18-29S-18E  
1980 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: DAVIDSON CHARLES A Well #: 18-1  
County: NEOSHO Total Vertical Depth: 1162 feet

Operator License No.: 33344  
Op Name: QUEST CHEROKEE, LLC  
Address: OKLAHOMA TOWER 210 PARK AVE.,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1016		149 SX CMT.
SURF	8.625	23		4 SX CMT.
T1	2.375	1012		

37.77

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2008 8:00 AM  
Plug Co. License No.: 33344 Plug Co. Name: QUEST CHEROKEE, LLC  
Proposal Rcvd. from: JERRY LESTER Company: QUEST CHEROKEE, LLC Phone: (620) 432-3519

Proposed Plugging Method: Run cement string to TD and plug from btm to top.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/19/2008 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was lowered down the 4.5" pipe and circulation established. The well was pumped full of cement from btm to top thru this cement string. The cement string was removed and the well topped off with cement. The wellhead was then hooked onto and squeezed. A total of 130 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DISTRICT #3

SEP 15 2008 AMD

CHANUTE, KS

INVOICED  
DATE 10-21-08  
INV. NO. 2009060570

Remarks:

Plugged through: CSG

District: 03

Signed

*Alan Dunning*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

SEP 29 2008

CONSERVATION DIVISION  
WICHITA, KS

PKT