

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01584-00-01
Spot: SWSESW Sec/Twnshp/Rge: 19-13S-17W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STAAB Well #: 1
County: ELLIS Total Vertical Depth: 3627 feet

Operator License No.: 33346
Op Name: TR SERVICE AND RENTAL, INC.
Address: 271 LK RD
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3627	0	w/100 sxs cmt
SURF	8.625	173	0	w/unknown sxs cmt

117.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2008 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: OZZIE VONAUSDALE Company: TR SERVICE AND RENTAL, INC. Phone: (785) 623-3014

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 13 sxs gel - 500# hulls.
Alt II 1286' cwc.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2008 10:20 AM KCC Agent: PAT STAAB

Actual Plugging Report:
Quality rigged to tubing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pumped 13 sxs gel - followed with 180 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Max. P.S.I. 300#. S.I.P. 200#.
Dup up 8 5/8" - cut hole in casing - casing was full of cement.

Perfs:

Top	Bot	Thru	Comments
3402	3418		

INVOICED
DATE 10-21-08
INV. NO. 2009060572

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #2091.

Plugged through: CSG

District: 04

Signed *Patrick Stueck*
(TECHNICIAN)

CM

PKT

RAYMOND OIL CO. #1 MADDEN 19-13-17W SW SE SW

Contr. COMPANY TOOLS ELLIS County

E2100KB Comm. 12/18/62 Comp. 3/7/63 IP PMP 94 BOPD. 5% WTR. GR 35/L/KC 3421-46

SMP Tops	Depth	Datum
DAK	750	+1350
ANH	1331	+769
TOP	3089	-989
HEEB	3350	-1250
TOR	3370	-1270
L/KC	3398	-1298
B/KC	3630	-1530
CONG	3640	-1540
TD	3734	-1634

Casing
 8" 173/140 SX:
 5" 3615:
 DST 3402-3433/60", SB, 1200' GAS, 30' O & GCM, 660' GSY MC, BHP 1135-1135#/30", FP 124-263#;
 DST 3437-53/60", SB, 1330' GAS, 675' GMO, 115' SW, BHP 1114-1037#/30", FP 118-290#;
 DST 3456-98/60", 150' SOCM, 120' SOC THIN M, BHP 1038-830#/30", FP 90-185#;
 DST 3534-68/45", WB/30", 40' USM, BHP 1165-1030#/30", FP 0-0#;
 COYD 3734: PERF 12/3421-24, 12/3430-33, A 1000: SWB 14 BOPH, NW, NATL: 8/3444-46, A 500: SWB 7.2 BHPH: POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS