

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23313-00-00  
Spot: SENESENW Sec/Twnshp/Rge: 12-8S-21W  
1890 feet from N Section Line, 2540 feet from W Section Line  
Lease Name: BETHELL Well #: 2  
County: GRAHAM Total Vertical Depth: 3588 feet

Operator License No.: 30076  
Op Name: ANDERSON, ANDY DBA A & A PRODU  
Address: PO BOX 100  
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1560		
PROD	4.5	3588	1043	160 SX
SURF	8.625	217	0	160 SX
TI	2.375	3588		

116.61

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2008 2:00 PM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: ANDY ANDERSON Company: A&A PRODUCTION Phone: (785) 567-8068

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/25/2008 9:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 3250' w/4 sxs cement on top.  
Shot casing at 1597' - not free.  
Allied pumped 50 sxs 60/40 pozmix - 4% gel with 100# hulls.  
Shot casing at 1043' - free - pulled to 1000'.  
Allied pumped 140 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled to 275' - pumped 40 sxs 60/40 pozmix - 4% gel with 100# hulls - circulated cement.  
Pulled casing out - topped off with 20 sxs cement - 8 5/8" full.

Perfs:

Top	Bot	Thru	Comments
3454	3459		
3330	3334		
3276	3278		

**INVOICED**  
DATE 10/22/08  
INV. NO. 2009060578  
**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**OCT 06 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM  
DWT

Form CP-2/6

OCT 02 2008