

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03820-00-00
Spot: NENENE Sec/Twnshp/Rge: 12-17S-11W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: KRAFT-PRUSA UNIT Well #: 2-6
County: BARTON Total Vertical Depth: 3409 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3403	0	125 SX
SURF	8.625	260	0	200 SX

110.79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2006 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perforations to plug 350' - 700' - 1415'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2008 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2403' - pumped 75 sxs cement.
Pulled tubing to 1900' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 800' - pumped cement until it circulated - closed backside and pumped approximately 40 sxs cement.
Max. P.S.I. 500#.
Pulled tubing out of well - filled casing with cement.
No way to hook to backside.
Cemented water in cellar and the backside took little to no fluid.

Perfs:

Top	Bot	Thru	Comments
3221	3239		
3160	3166		

INVOICED

DATE 10/22/08
INV. NO. 20090605 A

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 06 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: LEASE ALSO KNOWN AS ANDREA #6. SWIFT SERVICES, INC.-TICKET #14716.

Plugged through: TBG

District: 04

Signed Ray Dinkel PIRT
(TECHNICIAN)

CM

Form CP-2/3

SEP 26 2008

PKG

SUNRAY OIL CORPORATION #6 ANDREA 12-17-11W / 53
 NE NE NE


Contr. _____ BARTON _____ County

E. 1949RB Comm. 8-6-50 Comp. 9-15-50 IP 268 BOPD & 30% WTR
 PHY POT

Tops	Depth	Datum
HEEB	2960	
BR LM	3059	
LANS	3078	-1129
CONG	3374	-1425
BEW ARB	3392	-1443
ARB	3399	-1450
T. D.	3407	

Casing
 8" 260 CO 3250
 5" 3403 PERF 32 S, 3231-39
 ACID 500
 SWB 15 BOPH & 25% WTR

KRAFT PRUSA POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS