

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03845-00-00
Spot: NENWSE Sec/Twnshp/Rge: 12-17S-11W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KRAUTWURST Well #: 8
County: BARTON Total Vertical Depth: 3357 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3344	0	125 SX
SURF	8.625	273	0	200 SX <u>109.10</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2008 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-9231

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Junk in the hole at 1450'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2008 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1450' - pumped 155 sxs cement - circulated to surface.
Pulled tubing - tied onto backside - pumped 20 sxs cement - pushed back through casing.
Tied to tubing - pumped 25 sxs cement.
Max. P.S.I. 250#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3268	3273		
3222	3227		

INVOICED

DATE 10/22/08
INV. NO. 20090605 79

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 03 2008

CONSERVATION DIVISION
WICHITA, KS

SEP 26 2008

Form CP-2/3

PKG

SUNRAY OIL CORPORATION

#8

KRAUTWURST

53 12-17-11W
NE NW SE /

Contr. MOUSER DRILLING CO.

BARTON

County

E 1907

Comm.

Comp.

11-18-49

IP


235 BOPD

PHY POT

Tops	Depth	Datum
HEEB	2926	-1019
BR LM	3030	-1123
LANS	3045	-1138
ARB	3342	-1435
T.D.	3357	-1450

Casing

8" 273 AC ID 200
 5" 3344 SWB 3 BOPH
 AC ID 250
 NO INC
 SWB 15 BOPH



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS