

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15320-00-00
Spot: W2SWSE Sec/Twnshp/Rge: 12-17S-11W
660 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KRAFT-PRUSA UNIT Well #: 6-5
County: BARTON Total Vertical Depth: 3314 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3305	0	75 SX
SURF	8.625	278	0	100 SX

107.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2008 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-9231

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2008 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3100' - pumped 50 sxs cement with 100# hulls.
Pulled to 2770' - pumped 13 sxs gel and 15 sxs cement.
Pulled to 1420' - pumped 150 sxs cement with 200# hulls - circulated to surface.
Pulled tubing - squeezed with 50 sxs cement. Max. P.S.I. 500#.
Tied to backside - pumped 20 sxs cement. Max P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3250	3254		
3204	3208		
3175	3179		

INVOICED

DATE 10/22/08
INV. NO. 20090605 79

Remarks: LEASE ALSO KNOWN AS KRAUTWURST FEE #5. SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 03 2008

CONSERVATION DIVISION
WICHITA, KS

SEP 26 2008

PKT

12-17-11W

TRANSWESTERN OIL CO

#5

KRAITWURST FEE

CWL SW SE

Contr. _____ Barton _____ County

E 1891 Comm. 5-5-41 Comp. 5-19-41 IP 3000 BOPD

Tops	Depth	Datum
LANS	3008	
ARB	3302	
TD	3314	

Casing
 8" 277
 5" 3303

 1700' OIL 3314

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS