

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24645-00-00
Spot: NESENW Sec/Twnshp/Rge: 1-17S-15W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CHURCH Well #: 1
County: BARTON Total Vertical Depth: 3474 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3472 | 0 | 125 SX |
| SURF | 8.625 | 438 | 0 | 225 SX |

112.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2008 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Revd. from: KEVIN WILES Company: AMERICAN WARRIOR, INC. Phone: (620) 275-9231

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 14 sxs gel - 600# hulls.
Emergency plug with rig over the hole.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2008 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3450' - pumped 50 sxs cement with 100# hulls.
Pulled to 2972' - pumped 14 sxs gel.
Pulled to 1500' - pumped 175 sxs cement with 200# hulls - circulated cement to surface.
Pulled tubing - tied onto casing - pumped 25 sxs cement - circulated out backside.
S.I.P. 250#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------------|
| 3472 | 3474 | | OPEN HOLE ARBU |

INVOICED

DATE 10/22/08
INV. NO. 20090605 79

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 03 2008

CONSERVATION DIVISION
WICHITA, KS

SEP 26 2008

PKA

PELICAN HILL OIL & GAS
SAN CLEMENTE CA 92672

1-17S-15W
100'E, C N/2 SE NW

1 CHURCH

site: 5-3/4 N OF OLMITZ KS
contr: VONFELDT DRILLING # 1
opd: RANDALL KILIAN

city: BARTON
field: LEOVILLE

API 15-009-24645

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

| | | | | |
|------------------|-------------------|--------------------|----------------------|-----------------------|
| fr date 11/12/97 | spc date 11/17/97 | drig comp 11/24/97 | card issued 02/16/98 | last revised 02/16/98 |
|------------------|-------------------|--------------------|----------------------|-----------------------|

ELV: 1976 KB, 1971 GL LOG

| tops..... | depth/ datum |
|------------|--------------|
| ANH..... | 981 + 995 |
| B/ANH..... | 1009 + 967 |
| TOP..... | 2927 -951 |
| HEEB..... | 3158 -1182 |
| TOR..... | 3174 -1198 |
| LANS..... | 3222 -1246 |
| BKC..... | 3448 -1472 |
| ARB..... | 3470 -1494 |
| RTD..... | 3472 -1496 |
| LTD..... | 3474 -1498 |

IP status:
OIL, P 20 BO & 15 BWPD, ARB 3472-3474 , 12/15/97
 NOTE: CORRECTION 2/16/98 - ORIG FR IN NE SE NW
 CSG: 8-5/8" 438 / 225 SX (ALT 1), 5-1/2" 3472 / 125 SX
 SHOWS: 3100-3103, 3178-3181, 3240-3245, 3252-3257, 3292-3296, 3384-3389, 3472-3474
 NO CORES
 DST (1) 3444-3472 (ARB), / 30-30-30-45, 200' GIP, REC
 190' CLEAN GSY OIL, 90' HOCM ISIP 951# FSIP 945#
 IFP 10# -63# FFP 68# -110# IHP 1666# FHP 1713#
 TRGT ZN: LKC, ARB (OIL), PTD 3400 (ARB), MICT - CO TO 3274, (ARB OH), BAIL FL AT 2900, FU 600' FIH (EXCLNT SHW MO), ONFU 1575' FL, BAIL 38.4 BF/12 HRS, BAIL 4 HRS UNTIL CLEAN, FL DROPPED 100'/4 HRS, BAIL 2 BFPH (TR SW ON BTM), NAT, WKEND FU 2575' FL, SET 2-7/8" TBG AT 3445.33, NO PKR, POP, IPP 20 BO & 15 BWPD. 12/15/97 (TOP, TOR & LKC PAY.

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS