

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23548-00-00  
Spot: NESWSENE Sec/Twnshp/Rge: 34-21S-14W  
2000 feet from N Section Line, 700 feet from E Section Line  
Lease Name: VIOLET-MORTON Well #: 1-34  
County: STAFFORD Total Vertical Depth: 3850 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD  
GARDEN CITY, KS 67846

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 311        |             | WITH 300 SX CMT |

125.13

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2008 12:45 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: STEVE STEPHENS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 3750' WITH 50 SX CMT. 2ND PLUG AT 880' WITH 50 SX CMT. 3RD PLUG AT 340' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 09/24/2008 2:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 3750' WITH 50 SX CMT. 2ND PLUG AT 880' WITH 50 SX CMT. 3RD PLUG AT 340' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:


**INVOICED**  
DATE 10/22/08  
INV. NO. 2009060579

RECEIVED  
KANSAS CORPORATION COMMISSION  
**OCT 06 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed

Stephen J. Pfeifer  
(TECHNICIAN)