

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01404-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 27-8S-19W
4970 feet from S Section Line, 5060 feet from E Section Line
Lease Name: GREEN A Well #: 2
County: ROOKS Total Vertical Depth: 3434 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3434	0	w/unknown sxs cmt
SURF	8.625	179	0	w/unknown sxs cmt

111.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2008 9:00 AM
Plug Co. License No.: 33137 Plug Co. Name: GASCHLER WELL SERVICE LLC
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Operator working over well. Got down to 2165'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2008 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1900' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls - had circulation.
Pulled tubing to approximately 1000' - pumped 65 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing.
Hooked onto backside. Pressure to 200# with less than 1/4 bbl. S.I.P. 200#.
Hooked to 5 1/2" casing - pumped 25 sxs 60/40 pozmix - 4% gel. S.I.P. 200#.

Perfs:

INVOICED
DATE 10/22/08
INV. NO. 2009060580

Remarks: ALLIED CEMENTING COMPANY-TICKET #35001.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

OCT 03 2008

CONSERVATION DIVISION
WICHITA KS

SEP 26 2008

PT

27-8-19W
NW NW NW

W. L. Hartman #2 Green A

Contr. W. L. Hartman Rocks County

E 2001 Comm. 7-18-47 Comp. 10-17-47 IP 30 BOPD

Tops	Depth	Datum	Casing
			8" 179
ANH	1115		5" 3430
			2100' OIH/7 hrs
			Swb 115 BO/5½ hrs
LANS	3172		
ARB	3430		
T. D.	3431½		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

2009 08 43