

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04783-00-00
Spot: NESESE Sec/Twnshp/Rge: 35-19S-12W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: JOHANNING Well #: 8
County: BARTON Total Vertical Depth: 3345 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3337	0	150 SX
SURF	8.625	168	0	150 SX

108.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2008 1:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY Phone: (918) 494-8928

Proposed Plugging Method: Ordered 360 common cement - 300 gallons acid.
Junk in the hole at 425'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2008 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tubing and rods ate off at 369'.
Ran in with overshot - got nothing.
Drilled 6 to 8 feet with tricone bit and power swivel.
Ran in with mill shoe - probably out of casing.
Ran in with notched collar on tubing to 438'.
Spotted 300 gallons acid. Let set 45 minutes - pumped 100 sxs cement.
Pulled tubing to 30' and packed off in tubing head - pumped 250 sxs cement
Max. P.S.I. 350#. S.I.P. 200#.
Circulated out surface pipe.
Topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3332			OH
3307	3312		
3220	3226		
3156	3164		
3140	3144		
3126	3130		
3105	3116		
3082	3088		

INVOICED
DATE 10/22/08
INV. NO. 2009060583

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 08 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY-TICKET #33133.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

PKT

OCT 06 2008

35-19-12W
NE SE SE

W L HARTMAN

#8 JOHANNING


Contr. W L HARTMAN BARTON County

E 1804 RB Comm. Comp. 5-14-54 IP 25 BOPD

Tops	Depth	Datum
TOP	2706	-902
HEEB	2946	-1142
BR LM	3065	-1261
LANS	3082	-1278
B/KC	3324	-1520
CONG	3333	-1529
ARB	3336	-1532
ID	3345	-1541

Casing
 8" 168
 5" 3334
 CO 3345

HAMMER POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS